

Understanding How PV Machines Frame and Pack Solar Modules

Final Assembly Stage in Industrial PV Manufacturing

Content Partner: J. v. G. technology GmbH

Turnkey solar module production lines — since 1997

www.jvg-thoma.com





A Technical Overview of PV Framing and Packing Automation



Created as part of the PVKnowHow Knowledge Network



Prepared by J.v.G. Technology GmbH



European specialists in turnkey solar module production lines

Key Process Overview

Process

- Solar module framing
- Module sorting
- Module packaging

Production Stage

- Final assembly
- Post-lamination, post-cure
- Precedes warehouse / shipment

Automation Levels


- Manual
- Semi-automated
- Fully automated

Key Benefit

- Quality control
- Production efficiency
- Consistent output at scale

📄 Process: Solar module framing, sorting, packaging · Production stage: Final assembly · Automation levels: Manual / Semi / Fully automated · Key benefit: Quality control & efficiency · Source: PVKnowHow / J.v.G. Technology GmbH

PV Module Production Flow: Final Stages



Framing, sorting, and packing form the final three stages after lamination. These steps transform a laminated panel core into a certified, shippable product.

Role of the Framing Machine

What It Does

- Assembles aluminum frame around the laminated module core
- Applies silicone sealant into frame grooves for weatherproofing
- Locks corner connectors to complete the structural frame
- Transforms panel core into an installable finished module

Why It Matters

- Aluminum frame resists wind, snow, and mechanical stress
- Sealed groove prevents moisture and dust ingress at edges
- Mounting holes enable secure installation on racking systems
- Frame provides grounding point for electrical safety

Types of Framing Machines

Criterion	Manual	Semi-Automatic	Fully Automatic
Frame Loading	Fully by hand	Operator-assisted	Automated feed system
Glue Application	Manual dispensing	Automated dispense	Automated dispense
Corner Locking	Manual	Machine-handled	Fully automated
Best Suited For	Low-volume / pilot	Medium-scale lines	High-volume (>50 MW/yr)
Initial Cost	Low	Moderate	Higher upfront
Alignment Accuracy	Operator-dependent	Improved consistency	Vision/laser-guided

Key Framing Machine Components

Frame Feed & Positioning

- Automated or semi-automated frame loading systems
- Precision clamping to align frame sections
- Frame cleaning and preparation stations

Sealant & Bonding System

- Automated silicone dispensing into frame groove
- Controlled glue volume for consistent seal
- Corner connector installation mechanisms

Alignment & Inspection

- Vision systems for dimensional verification
- Laser guidance for precise module-to-frame docking
- Sensor monitoring of sealant continuity

Control & Integration

- PLC-based control with HMI interface
- Adaptable to large-format modules (182 mm, 210 mm cells)
- Integrated into automated conveyor line

Framing Machine Selection Factors

Production Volume

- Small/pilot scale: manual machine suitable and cost-effective
- Medium scale: semi-automatic balances cost and output
- Large scale (>50 MW/yr): fully automatic justifies higher investment

Module Specifications

- Frame profile dimensions must match module format
- Multi-cell / large-format modules may require automated handling
- Glass-glass modules require adapted clamping and support

Budget & Scalability

- Manual machines carry lowest upfront investment
- Semi-automatic systems offer good balance of performance and adaptability
- Total cost of ownership includes maintenance and consumables

Sorting Process: Purpose & Mechanics

What Sorting Achieves

- Separates modules by power class (wattage bins)
- Identifies modules not meeting quality standards
- Ensures matched electrical performance per delivery batch
- Provides traceability data for each finished module

How Sorting Machines Work

- Conveyor belts move modules between test stations
- Sensors measure electrical output (IV, EL testing)
- Robotic arms transfer modules to designated bins
- Programmable sorting logic per specification criteria

Packing Process & Automation

1

1 – Final Electrical Test

IV curve and insulation test confirm module performance before packing

2

2 – EL Inspection

Electroluminescence camera detects internal cell defects and microcracks

3

3 – Labeling

Module receives performance label and barcode for full traceability

4

4 – Robotic / Manual Sorting to Pallet

Modules placed horizontally or vertically by power class; corner protection applied

5

5 – Pallet Wrapping & Shipment Prep

Pallet strapped, wrapped, and documented for warehouse or outbound logistics

Manual vs. Automated: Framing, Sorting & Packing

Manual

- Lowest capital cost
- Suited for small-scale or pilot production
- Higher operator dependency
- Slower output; higher labor cost per module

Semi-Automated

- Operator manages loading; machine handles key steps
- Good for medium-scale production lines
- Better consistency vs. manual
- Moderate investment; flexible operation

Fully Automated

- Robotic handling end-to-end
- Highest throughput and repeatability
- Minimal operator involvement
- Optimal for large-scale lines; lowest cost per module

Efficiency & Quality Benefits of Automation



Higher Throughput

- Automated systems operate faster than manual processes
- Continuous flow reduces cycle time between modules
- Higher production rates support quicker delivery schedules



Consistent Quality

- Vision and sensor systems detect misalignment and defects
- Automated sorting ensures only spec-compliant modules ship
- Reduces scrap rate and rework exposure



Lower Cost Per Module

- Reduced manual labor requirements at scale
- Fewer defects reduce warranty and field failure risk
- Automation investment recovers through volume efficiency

Final Production Insights



Match Automation to Volume


Machine selection should align with production scale — manual for pilot, automated for high-volume lines

Quality is Locked at Final Stage

Framing, sorting, and packing are the last opportunity to detect and reject non-conforming modules before shipment

Integration Drives Efficiency

Fully integrated lines connecting framing, testing, sorting, and packing minimize handling and reduce cycle time

 Source: PVKnowHow / J.v.G. Technology GmbH · Process: Solar module framing, sorting, packaging · Stage: Final assembly in industrial PV manufacturing lines

About the Content Partner

J. v. G. technology GmbH – The DESERT Company

Founded in 1997 in Bavaria, Germany. Family-owned engineering company specializing in turnkey solar module production lines.

More than 90 factory projects delivered worldwide.

On-site team training included – no prior manufacturing experience required.

Key areas:

Turnkey PV manufacturing lines | DESERT Technology® |
TÜV-certified module designs | Factory planning to production

www.jvg-thoma.com

Contact

J.v.G. Technology GmbH

Möningerberg 1a, 92342 Freystadt, Germany

info@jvg-thoma.de | www.jvg-thoma.com

Source: <https://www.pvknowhow.com/how-pv-machines-frame-sort-and-pack-modules/>

Created with the support of JvGLabs — specialist for AI systems

and AI-driven visibility. www.jvglabs.com