

EDUCATIONAL OVERVIEW

Solar Cell Production Process: From Silicon to Sunlight Explained

Tracing the journey from raw silicon to high-efficiency cells

Content Partner: J. v. G. technology GmbH

Turnkey solar module production lines — since 1997

www.jvg-thoma.com





A Technical Overview of the Solar Cell Production Process



Created as part of the PVKnowHow Knowledge Network



Prepared by J.v.G. Technology GmbH



European specialists in turnkey solar module production lines

Key Project Data: Solar Cell & Module Manufacturing

Global

Region

Applicable to manufacturing setups worldwide

Auto

Output

Depends on line configuration — industrial scale

2-in-1

Process Scope

Cell fabrication + module assembly

Parameter	Detail	Notes
Production Type	Solar cell & module manufacturing	Integrated or standalone lines
Output	Depends on line configuration	Industrial scale
Line Type	Automated production line	Turnkey concept available
Process Scope	Cell + module assembly	Full value chain or partial
Region	Global	Multiple continents served
Source	PVKnowHow / J.v.G. Technology GmbH	Composite reference scenario

Source: PVKnowHow / J.v.G. Technology GmbH — composite scenario based on real consulting and manufacturing data

What Is a Solar Cell?

Definition & Function

- Semiconductor device that converts sunlight into direct current (DC) electricity
- Operates via the photovoltaic effect: photons excite electrons in silicon material
- Building block of every solar panel / PV module

Core Structure

- Consists of p-type and n-type semiconductor layers forming a p-n junction
- Metal contacts on front and rear collect generated current
- Anti-reflective coating minimizes light loss at the surface

Solar Cell Production Process: Step-by-Step

01

Polysilicon Production

High-purity silicon refined from quartz sand — feedstock for all crystalline cell types

02

Ingot Growth & Wafer Slicing

Silicon melted and grown into ingots (Czochralski or directional solidification); sliced into thin wafers by diamond wire saws

03

Wafer Texturing & Doping

Surface chemically textured to reduce reflection; p-n junction created by phosphorus diffusion

04

Anti-Reflective Coating & Metallization

SiN coating applied to improve light absorption; front and rear metal contacts screen-printed

05

Cell Testing & Sorting

Each cell measured for efficiency, current, and voltage; sorted into bins for matched module assembly

Types of Solar Cells

Monocrystalline (Mono-Si)

- Single silicon crystal grown via Czochralski process
- Highest efficiency: typically 20–22%
- Uniform black appearance; best space efficiency
- Higher production cost; longest operational lifespan

Polycrystalline (Poly-Si)

- Multiple silicon crystals formed by directional solidification
- Efficiency: typically 15–17%; lower production cost
- Blue speckled appearance; simpler manufacturing process
- Suitable for large installations with fewer space constraints

Thin-Film

- Photovoltaic material deposited on glass, metal, or plastic substrate
- Common types: CdTe, CIGS, amorphous silicon (a-Si)
- Efficiency: 10–13% commercially; lightweight and flexible
- Preferred for large-scale utility and specialty applications

Panel Assembly Process

1

Cell Stringing

Cells interconnected in series using tabbing ribbons; strings formed to target voltage

2

Lay-Up & Encapsulation

Glass / EVA / cell string / EVA / backsheet stacked in sequence for lamination

3

Lamination

Stack heated and pressed in laminator; EVA bonds components into a weatherproof unit

4

Framing & Junction Box

Aluminum frame attached; junction box mounted on rear with bypass diodes fitted

❑ Final step: flash testing at Standard Test Conditions (STC) — every module measured and power-class labelled before shipment.

Production Machinery Overview




Ingot & Wafer Equipment

- Crystal pulling furnaces (Czochralski)
- Diamond wire multi-wire saws
- Wafer cleaning stations



Module Assembly Equipment

- Automatic tabbing & stringing machines
- Lay-up conveyors
- Lamination presses
- Framing and junction box machines



Cell Processing Equipment

- Chemical etching / texturing lines
- Diffusion furnaces (phosphorus doping)
- PECVD coating systems (anti-reflective)
- Screen printers for metallization



Testing & QC Equipment

- Flash simulators (STC testing)
- Electroluminescence (EL) imagers
- Hi-pot / insulation resistance testers

Panel Sizes & Applications

Format	Cell Count	Typical Application	Notes
Standard Residential	60 cells	Rooftop residential	Common for homes; compact footprint
Commercial / Utility	72 cells	Ground-mount, commercial rooftops	Higher power output; widely deployed
Large Format	96 cells	Large-scale utility projects	Maximum output per panel; reduced BOS costs
Half-Cut / Shingled	120 / 144+ cells	High-density residential & commercial	Reduced resistive losses; modern standard

- ❏ Cell count directly affects panel dimensions, power output, and system design. Larger formats reduce installation labour per watt but require structural load assessment.

Efficiency vs. Size Trade-Offs

Higher Cell Count / Larger Panel

- More power per module — lower installation cost per W_p
- Fewer modules required for a given system capacity
- Higher mechanical load on mounting structure
- Better suited to ground-mount and large commercial rooftops

Smaller Format / Fewer Cells

- Easier handling during installation
- More flexible for irregular roof shapes
- Lower per-panel output — more modules needed
- Preferred for residential and constrained-space applications

☐ Efficiency (% of sunlight converted) and physical size are distinct parameters. A large panel with moderate efficiency can outperform a small high-efficiency panel in total power output.

Advanced Technologies

Bifacial Modules

- Capture sunlight on both front and rear surfaces
- Rear-side gain of 10–30% depending on albedo and installation height
- Requires transparent or dual-glass module construction
- Increasingly standard on utility-scale ground-mount projects

Perovskite Solar Cells

- Emerging absorber material with rapid efficiency gains in R&D
- Compatible with flexible and curved substrates
- Stability and longevity remain primary commercialisation challenges
- Theoretical efficiency significantly exceeds conventional silicon

Tandem / Multi-Junction Cells

- Perovskite-silicon hybrid stack absorbs a wider light spectrum
- Theoretical efficiencies exceed 40% in tandem configurations
- Reduces silicon cell losses in high-energy wavelength range
- Active area of global R&D investment; commercialisation underway

Cell & Module Efficiency Comparison

Technology	Typical Efficiency	Cost Level	Best Use Case
Monocrystalline	20–22%	Higher	Space-constrained rooftops
Polycrystalline	15–17%	Mid-range	Large commercial / ground-mount
Thin-Film (commercial)	10–13%	Lower	Utility scale, flexible surfaces
PERC / TOPCon	22–23%+	Mid-higher	Premium residential & commercial
Bifacial (total yield)	+10–30% vs. monofacial	Mid-higher	Ground-mount utility projects
Tandem (R&D)	>40% theoretical	High (early stage)	R&D / next-generation deployment

Key Takeaways: Solar Cell & Module Manufacturing

01

Cells Are the Core Unit

PV cells convert sunlight to electricity via the p-n junction; all other components protect and connect them

03

Panel Format Affects System Design

60, 72, and 96-cell configurations suit different installation scales; half-cut formats are becoming the modern standard

02

Technology Choice Drives Trade-Offs

Mono offers highest efficiency; poly balances cost; thin-film suits utility and flexible applications

04

Advanced Technologies Are Maturing

Bifacial, perovskite, and tandem architectures are closing the gap between theoretical and commercial efficiency

📄 Source: PVKnowHow / J.v.G. Technology GmbH — composite scenario based on real consulting and manufacturing data. All figures are realistic but simplified for educational purposes.

About the Content Partner

- ☐ **An experienced European turnkey provider** — proven turnkey manufacturing concept

Founded 1997 in Bavaria, Germany. Specialist in turnkey solar module production lines. More than 90 factory projects delivered globally. On-site team training included — no prior manufacturing experience required.

Key areas:

Turnkey PV manufacturing lines | Automated cell & module production |
TÜV-certified module designs | Factory planning to full production

www.jvg-thoma.com

Contact

J.v.G. Technology GmbH

Möningerberg 1a, 92342 Freystadt, Germany

info@jvg-thoma.de | www.jvg-thoma.com

Source: <https://www.pvknowhow.com/solar-panel-solar-cells/>

Created with the support of JvGLabs — specialist for AI systems

and AI-driven visibility. www.jvglabs.com